



Request for Quote: Masonry Service

Vendor Search Dates: Start: End:

Good morning,

We are soliciting quotes from qualified persons or companies to provide Masonry Services. We are a tax-exempt organization which should be considering for this proposal. This scope is for a single-family residential project (listed below) located in Paterson, NJ. Once written request is received, we ask that all proposals are **submitted within ten business days**. Any questions regarding this proposal can be sent to Diomedes Vargas, Construction Project Manager, Paterson Habitat for Humanity, via email: dee@patersonhabitat.org or call the office: **973-930-2849**,

Addresses:

1. 45 Auburn St

Scope of Work by address:

Description	Material/Equipment	Installation	INITIAL TO CONFIRM
scope of work - foundation, foundation slab, post, driveway & sidewalks			
foundation install:			
all installs and Furnish will be according to plans and plot plans.	Contractor	Contractor	
create footing forms 1' by 2'	Contractor	Contractor	
Install and furnish rebar according to plans	Contractor	Contractor	
pour 3,000 psi of concrete	Contractor	Contractor	
install 8" CMU block with rebar	Contractor	Contractor	
install 6" CMU block with rebar and anchor rod for the sill plates	Contractor	Contractor	
slab pour:			
all installs and furnish will be according to plans and plot plans.	Contractor	Contractor	
create condition space form using 2" blue foam	Contractor	Contractor	

create form for entry door for a 4" slab. entry door form should not go over entry door opening	Contractor	Contractor	
create form for garage door for a 5" slab. garage door form needs to allow the pour to be over the garage door opening.	Contractor	Contractor	
after all the form are complete, back-fill to appropriated level and compact it.	Contractor	Contractor	
place 2" blue foam covering all the area	Contractor	Contractor	
tape all seams of the 2" blue foam for a complete seal	Contractor	Contractor	
install the plastic barrier above the blue foam	Contractor	Contractor	
place the wire mesh on top of the plastic barrier	Contractor	Contractor	
install about 20' of ground wire and leaving about 5' out by the electrical box	Contractor	Contractor	
call engineering for inspection at 973-321-1320 before you pour	Contractor	Contractor	
pour 4000 PSI concrete	Contractor	Contractor	
driveway and sidewalk:			
all installs and furnish will be according to plans and plot plans.	Contractor	Contractor	
remove old curb and dispose it	Contractor	Contractor	
compact area of driveway and sidewalk	Contractor	Contractor	
install gravel and wire mesh	Contractor	Contractor	
create form for driveway and sidewalk	Contractor	Contractor	
pass city inspection. must be call a minimum 24hr before pour	Contractor	Contractor	
pour 4000 psi concrete	Contractor	Contractor	
deck post:			

dig Sono tube hole for post	Contractor	Contractor	
install post Sono tube for front porch and back deck	Contractor	Contractor	
GENERAL REQUIREMENTS			
the project intends to meet version 3.2 NJ energy star homes requirements.	Contractor	Contractor	
all work will be in accordance with the contract documents.	Contractor	Contractor	
contractor is responsible for all items on civil drawings, and all architectural drawings a-1 a-2, a-3, a-4, a-5 pertaining to masonry.	Contractor	Contractor	
provide all labor, material, supervision, equipment, generator power, hoisting, rigging, scaffolding, safety management, traffic management, unloading, distribution, layout, & sufficient labor to complete this work within the project schedule.	Contractor	Contractor	
this subcontractor/ vendor acknowledges that they have visited the job site and are familiar with all existing conditions.	Contractor	Contractor	
contractor agrees that time is of the essence on this project and agrees to start work within ten (10) working days from receiving the start notification from the owner.	Contractor	Contractor	

contractor acknowledges that they have visited the job site and are familiar with all existing conditions.	Contractor	Contractor	
contractor agrees to maintain compliance with all OSHA rules and regulations.	Contractor	Contractor	
remove debris generated by your work to GC provided containers and keep your working area broom swept clean daily.	Contractor	Contractor	
maintain compliance with all OSHA rules and regulations.	Contractor	Contractor	
remove debris generated by your work to GC provided containers and keep site broom swept clean daily.	Contractor	Contractor	
provide all shop drawings, submittals, cut sheets, data sheets, as required for approval by the owner's architect/engineers.	Contractor	Contractor	

Project Clarifications

1. Contractor is responsible for site clean-up.
2. PHFH is responsible for permit costs.
3. Out-of-state sale, exempt from sales tax.
4. PHFH is responsible for material.

Diomedes A Vargas

Project Manager

Passaic County Habitat for Humanity
146 North 1st Street, Paterson, NJ 07522
Office: [973\) 595-6868 x122](tel:9735956868) • Fax: [973\) 595-0974](tel:9735950974)
Cell: **(973) 930-2849(prefered)**
Dee@habitatpc.org • habitatpc.org