



Request for Quote: Retaining wall and Foundation Services

Vendor Search Dates: Start: End:

Good morning,

We are soliciting quotes from qualified persons or companies to provide Retaining wall and Foundation Services. We are a tax exempt organization which should be taking into account for this proposal. This scope is for a single-family residential projects (listed below) located in Paterson, NJ. Once written request is received, we ask that all proposals are **submitted within 10 business days**. Any questions regarding this proposal can be sent to Diomedes Vargas, Construction Project Manager, Paterson Habitat for Humanity, via email: dee@patersonhabitat.org or call the office: **973-930-2849**, or Felix E. Rodriguez, Property Manager, via email: felix@patersonhabitat.org or call, **973-595-6868 ext 109**.

Addresses:

1. 101 North 3rd st Paterson NJ

Scope of Work by address:

- Demo scope of work:
 - Demo crumbling wall to the left.
 - Demo Small portion of wall in the left side of property. The wall attached to the building on the left.
- Pour Footing Scope of work
 - Create forms and pour for 8 different footing for different sizes.
 - Dimensions:
 - 1st footing: (top section is W: 11'-4" L:6'-2' H: 2')(bottom Section is W:4'-2" L: 16' H: 4')
 - 2nd footing: W: 7'-0" L: 6'-2" H: 2'
 - 3rd footing: W: 5'-1" L: 12' H: 4'
 - 4th footing: W: 16' L: 16' H: 4'
 - 5th Footing: W:9' L: 9' H: 2'
 - 6th footing: W: 3' L: following the foundation walls dimensions H: 9"
 - 7th footing: W:17'-4" L:8'-8" H: 2'
 - 8th footing: W: 5'-6" L 6' H: 2'
 - 9th footing: W: L: 6' H: 1' 6"
- Retaining wall scope of work:
 - Install 5 retaining wall and one regular wall for the stair section
 - Left retaining wall: W: 8" L: 38' H:11'
 - Top Retaining wall: W: 25' L: 8" H: 13' to 15'
 - Right Retaining wall: W: 8" L: 55' H 13'
 - Stair case middle: W: 3' L: 11' H: 13'

- Neighbor retaining wall: W: 10” L:15’ H:7’ 6”
- Foundation:
 - Install blocks for a W: 18’ 6” L:42’ 2” H:12’
 - Install metal lath
 - Install rebar for foundation block wall support.
 - Backfill block wall with cement/mortal
 - Install j-bolt in order to install plates in top of foundation wall.
 - Waterproofing foundation
- Excavation or backfilling were is needed to prep for the wall.

Project Clarifications

1. Contractor is responsible for site clean up
2. PHFH is responsible for permit costs.
3. Out-of-state sale, exempt from sales tax
4. PHFH is responsible for material.

Diomedes A Vargas

Project Manager

Passaic County Habitat for Humanity

146 North 1st Street, Paterson, NJ 07522

Office: [973\) 595-6868 x122](tel:9735956868) • Fax: [973\) 595-0974](tel:9735950974)

Cell: **(973) 930-2849(prefered)**

Dee@habitatpc.org • habitatpc.org