



Vendor Search Dates: Start: End:

Good morning/evening,

We are soliciting quotes from qualified persons or companies to provide Masonry Services. This scope of work is for one commercial project (listed below) located in Paterson, NJ. Once written request is received, we ask that all proposals are submitted within 5 days. Any questions regarding this proposal can be sent to Diomedes Vargas Project manager via dee@patersonhabitat.org or call 973-930-2849

Address:

1. 177-191 Harrison St

Scope of Work at each location:

- Curb- Sidewalk and Driveway prep
 - 59' liner feet of curb
 - Removal of old curb and disposal to a location chosen by PHFH
 - Concrete Curb Installation Labor
 - Basic labor to install concrete curb with favorable site conditions. Layout finished height and slope. Lightly grade and remove loose soil. Set forms and reinforcing. Pour and finish concrete. Excavation, gravel base layer, compaction or hardscape demolition not included. Includes planning, equipment and material or forms needed to perform task, area preparation and protection, setup and cleanup.
- Sidewalk and driveway aprons
 - 5' X 34' Sidewalk = 170sf
 - 11' X 3' Driveway apron = 33sf
 - 18' X 10' Driveway apron = 180sf
 - 8' X 5' Sidewalk = 40sf
 - 6'6" X 5' Slab under roof over door = 33sf
- Foundation Slab install
 - 6' X 45' at 4"d
 - 12' X 40' at 5"d

Clarifications

- Contractor must provide site generator and forms
- Materials taken from site for form building will be back charged to contractor
- PHFH will provide onsite restroom
- PHFH will provide propane and heating station upon request

Diomedes Vargas
Construction Project Manager
Passaic County Habitat for
Humanity
Dee@habitatpc.org
973-595-6868 ext. 122
Cell: 973-930-2849